

San Francisco Public Utilities Commission Water System Improvement Program and Its Seismic Requirements




*Luke Cheng
Engineering Management Bureau
San Francisco Public Utilities Commission*


Outline

- Hetch Hetchy Water System
- Water System Improvement Program (WSIP)
- Seismic Requirements
- Current Status
- Summary

Bay Area Water Districts



SFPUC System & Service Area



Hetch Hetchy Water System

260 million gallons

167 miles

2.6 million people



A Regional System

280 miles of pipelines, 60+ miles of tunnels,
11 reservoirs, 5 pump stations and 2 water
treatment plants



The map illustrates the Hetch Hetchy Regional Water System, highlighting three major faults: the San Andreas Fault, Hayward Fault, and Calaveras Fault. The system's infrastructure includes the Tuolumne River, various reservoirs (San Antonio, Crystal Springs, Lake Lloyd, Lake Eleanor, Hetch Hetchy, Lake Eleanor, Priest, Moccasin, New Don Pedro), and several powerhouses (Harry Tracy, Holm, Canyon, Kirkwood, Priest, Moccasin). Key tunnels and pipelines shown are the Crystal Springs Bypass, Pulgas, Foothill, and San Joaquin Pipelines, along with Bay Division Pipelines No. 1, 2, 3, and 4. The map also identifies major cities (San Francisco, San Jose, Palo Alto) and geographical features like San Francisco Bay, Half Moon Bay, and Yosemite National Park.



Water System Improvement Program

- Voter approved November 2002
- \$4.4 Billion
- 80+ projects in 7 counties
- Completion late 2014



Seismic Requirements

- Goals
 - Seismic Hazards
 - Seismic Criteria

Delivery Goals

24 hours after major EQ

30 days after major EQ

Major EQs

- M7.8 San Andreas
- M7.1 Hayward
- M6.8 Calaveras




Delivery Goals After a Major EQ

- Deliver 229 MGD (winter demand) within 24 hours after a major EQ
- 70% of turnouts within each customer group will receive the water
- 90% reliability

Customer Groups

- Santa Clara/Alameda/South San Mateo County
- Northern San Mateo County
- City of San Francisco



Post-EQ Recovery Goals

- Deliver 300 MGD (average day demand) within 30 days after the earthquake
- Assume resources and infrastructure are available

Seismic Hazards

- Fault Rupture
 - Magnitude
 - Locations
- Ground Motions
 - Design earthquakes
- Slope Instability
- Liquefaction



Seismic Criteria

- Buildings & Building-like Structures
- Non-building Structures
- Non-structural Elements
- Tanks
- Covered Reservoirs
- Pipelines
- Dams
- Tunnels
- Special Structures

Buildings & Building-like Structures



- International Building Code (IBC)
- California Building Code (CBC)
- ASCE/SEI-7

Non-building Structures



- International Building Code (IBC)
- California Building Code (CBC)
- ASCE/SEI-7

Non-structural Elements

- International Building Code (IBC)
- California Building Code (CBC)
- ASCE/SEI-7
- ASCE Standards, i.e. *Guide to Improved Earthquake Performance of Electric Power Systems*



Tanks

- International Building Code (IBC)
- California Building Code (CBC)
- ASCE/SEI-7
- AWWA D100



Covered Reservoirs

- International Building Code (IBC)
- California Building Code (CBC)
- ASCE/SEI-7
- ACI350 & ACI350.3



Pipelines



- *ALA, Seismic Guidelines for Water Pipelines*
- Standards/Manuals by ASCE, ASME, AWWA, API etc.

Dams



- Guidelines by
 - California Department of Water Resources' Division of Safety of Dams (DSOD)
 - United States Society of Dams (USSD)

Tunnels



- 2-D or 3-D soil-structure interaction (SSI) analysis depending on the structural layout and dimensions.
- Methods proposed by
 - Y.M.L Hashash *et al.*, 2001
 - J. Penzien, 2000
 - Jaw-Nah Wang, 1993
 - Ostadan and Penzien, 2001

Special Structures



- Reservoir Outlet Towers
 - USACE Manuals, i.e. *Structural Design and Evaluation of Outlet Works*
- Bridges
 - California Department of Transportation (Caltrans) Bridge Design Specifications

Status of WSIP Regional Projects

As of July 1, 2009

Active Phase	No. Projects
Planning	2
Design	11
Bid & Award/Construction	11
Multiple Phases	11
Closeout/Completed	10

Regional Program Performance

As of July 1, 2009

	All Improvements	
Project Phase	Percent Planned	Percent Actual
All Phases	16.7%	16.6%
Planning	97.3%	96.4%
Design	75.8%	74.6%
Construction	6.1%	6.2%
Close-Out	23.4%	21.8%

Summary

- SFPUC WSIP is one of the largest water infrastructure programs in the US.
- The Program's seismic requirements incorporate the latest seismic codes and standards.
- As of July 2009, overall, program performance is very close to as planned.

Thank You

